# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT7804

## APPROVED SCHEDULE - B

**Tender Notification No: EE/BTP/BBMP/E-PMT/05/2013-14, Date: 11.07.2013**

**Improvements of main roads and cross roads from 13th cross to 18th cross roads from 1st cross to 4th cross roads and drains in Jakkur layout in ward no. 07, Kodigehalli sub division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of NARAYANASWAMY A G | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 12705 | Removing BS Slab of drain and stacking. | Sqm | 43.0 | Rupees Forty Three Only |
| 2 | 8893.5 | Refixing stone slabs of drains and pointing in CM 1:3. | Sqm | 59.0 | Rupees Fifty Nine Only |
| 3 | 3811.5 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick) | Cum | 306.0 | Rupees Three Hundred Six Only |
| 4 | 6160 | KSRRB M300-1: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3. | Sqm | 57.5 | Rupees Fifty Seven and Fifty Paise Only |
| 5 | 30800 | KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. | Sqm | 3.0 | Rupees Three Only |
| 6 | 6622 | KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. | Cum | 1000.0 | Rupees One Thousand Only |
| 7 | 30800 | KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. | Sqm | 42.0 | Rupees Forty Two Only |
| 8 | 770 | KSRRB M500-18. Providing and laying semi dense bituminous concrete<br>25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver | Cum | 9405.0 | Rupees Nine Thousand Four Hundred Five Only |

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

| | | | | | |
|---|---|---|---|---|---|
| 9 | [illegible]175 | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km | Cum | 69.87 | Rupees Sixty Nine and Eighty Seven Paise Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92